

PROJECT MASTER QUANTITY TAKEOFF SUMMARY

Executive Scope & Quantity Analysis Report (Without Cost Data)

PROJECT NAMEMulti-Story Building Construction / Residential Project

PREPARED BYArchitectural Design & Quantity Surveying Department

SCOPE OF WORKWall, Floor, Door, and Window Material Quantity Analysis & Schedule Verification

Quantity Takeoff Summary by Category

1. Door Material Takeoff

Total Quantity:

254.01 SF / 24 NOS

Work Scope:

Includes Double-Glass Doors and Single Flush Doors (Frames, Panels, and Glass elements across all levels).

2. Floor Material Takeoff

Total Quantity:

4,712.00 SF / 2,224.64 CF

Work Scope:

Includes Floor Tiles, Concrete Slabs, Carpet Finish, and Site Earth Filling/Sub-base preparation.

3. Wall Material Takeoff

Total Quantity:

7,492.00 SF / 2,889.68 CF

Work Scope:

Includes Masonry Blockwork, Internal & External Plastering, Painting, Teak Finish, and Wall Insulation.

4. Window Material Takeoff


Total Quantity:

33 NOS

Work Scope:

Includes Casement Windows with Glass Panes, Sash, and Architectural Trims across Levels 1 to 3.

Total Summary			
Item No	Description	Total Quantity	Estimation: Cost
1	Door Material	254SF/24NOS	₹ 83,100.00
2	Floor Material	2224.64CF/4712	₹ 390,870.00
3	Wall Material	2889.68CF/7492SF	₹ 788,440.60
4	Window Material	33NOS	₹ 55,850.00
		Sub:Total	₹ 1,318,260.60
		Contingencies(3%)	₹ 39,547.82
		Grand:Total	₹ 1,357,808.42



www.autodesk.com/revit

Consultant
Address
Address
Phone
Fax
e-mail

Scale 1 : 80

Door Material Takeoff									
Family and Type	Material: Name	Count	Level	Width	Height	Material: Cost	Labour:Cost	Total:Rate	Total:Amount
Double-Glass 2: 72" x 78"	Door - Frame	1	Level 1	6' - 0"	6' - 6"	₹ 2,500.00	₹ 500.00	₹ 3,000.00	₹ 3,000.00
Double-Glass 2: 72" x 78"	Door - Panel	1	Level 1	6' - 0"	6' - 6"	₹ 8,000.00	₹ 1,000.00	₹ 9,000.00	₹ 9,000.00
Double-Glass 2: 72" x 78"	Glass	1	Level 1	6' - 0"	6' - 6"	₹ 1,500.00	₹ 300.00	₹ 1,800.00	₹ 1,800.00
M_Single-Flush: 0762 x 2032mm	Door - Frame	1	Level 1	2' - 6"	6' - 8"	₹ 1,200.00	₹ 300.00	₹ 1,500.00	₹ 1,500.00
M_Single-Flush: 0762 x 2032mm	Door - Panel	1	Level 1	2' - 6"	6' - 8"	₹ 3,500.00	₹ 500.00	₹ 4,000.00	₹ 4,000.00
M_Single-Flush: 0915 x 2134mm	Door - Frame	3	Level 1	3' - 0"	7' - 0"	₹ 1,500.00	₹ 400.00	₹ 1,900.00	₹ 5,700.00
M_Single-Flush: 0915 x 2134mm	Door - Panel	3	Level 1	3' - 0"	7' - 0"	₹ 4,000.00	₹ 600.00	₹ 4,600.00	₹ 13,800.00
Double-Glass 2: 72" x 78"	Door - Frame	1	Level 2	6' - 0"	6' - 6"	₹ 2,500.00	₹ 500.00	₹ 3,000.00	₹ 3,000.00
Double-Glass 2: 72" x 78"	Door - Panel	1	Level 2	6' - 0"	6' - 6"	₹ 8,000.00	₹ 1,000.00	₹ 9,000.00	₹ 9,000.00
Double-Glass 2: 72" x 78"	Glass	1	Level 2	6' - 0"	6' - 6"	₹ 1,500.00	₹ 300.00	₹ 1,800.00	₹ 1,800.00
M_Single-Flush: 0762 x 2032mm	Door - Frame	1	Level 2	2' - 6"	6' - 8"	₹ 1,200.00	₹ 300.00	₹ 1,500.00	₹ 1,500.00
M_Single-Flush: 0762 x 2032mm	Door - Panel	1	Level 2	2' - 6"	6' - 8"	₹ 3,500.00	₹ 500.00	₹ 4,000.00	₹ 4,000.00
M_Single-Flush: 0915 x 2134mm	Door - Frame	3	Level 2	3' - 0"	7' - 0"	₹ 1,500.00	₹ 400.00	₹ 1,900.00	₹ 5,700.00
M_Single-Flush: 0915 x 2134mm	Door - Panel	3	Level 2	3' - 0"	7' - 0"	₹ 4,000.00	₹ 600.00	₹ 4,600.00	₹ 13,800.00
M_Single-Flush: 0762 x 2032mm	Door - Frame	1	Level 3	2' - 6"	6' - 8"	₹ 1,200.00	₹ 300.00	₹ 1,500.00	₹ 1,500.00
M_Single-Flush: 0762 x 2032mm	Door - Panel	1	Level 3	2' - 6"	6' - 8"	₹ 3,500.00	₹ 500.00	₹ 4,000.00	₹ 4,000.00
Grand total: 24		24						Total:Unit	₹ 83,100.00

Floor Material Takeoff								
Family and Type	Material: Name	Level	Material: Area	Material: Volume	Material: Cost	Labour:Cost	Total:Rate	Total:Amount
Floor: Generic 150mm	Default Floor	Level 1	1752	862.31	₹ 60.00	₹ 25.00	₹ 85.00	₹ 148,920.00
Floor: Generic 150mm	Default Floor	Level 2	1453	714.9	₹ 60.00	₹ 25.00	₹ 85.00	₹ 123,505.00
Floor: Generic 150mm	Default Floor	Level 3	1137	559.73	₹ 60.00	₹ 25.00	₹ 85.00	₹ 96,645.00
Floor: Generic 150mm	Carpet (2)	Level 4	14	0	₹ 80.00	₹ 15.00	₹ 95.00	₹ 1,330.00
Floor: Generic 150mm	Default Floor	Level 4	178	87.71	₹ 60.00	₹ 25.00	₹ 85.00	₹ 15,130.00
Floor: Generic 150mm	Site - Earth	Level 4	178	0	₹ 20.00	₹ 10.00	₹ 30.00	₹ 5,340.00
Grand total: 6			4712	2224.64			Total:Unit	₹ 390,870.00

Wall Material Takeoff										
Family and Type	Material: Name	Base Constraint	Length	Unconnected Height	Material: Area	Material: Volume	Material: Cost	Labour: Cost	Total: Rate	Total: Amount
Basic Wall: Generic - 140mm Mason	Masonry - Concrete Block	Level 1	9' - 2"	10' - 0"	85	39.11	₹ 65.00	₹ 25.00	₹ 90.00	₹ 3,519.90
Basic Wall: Generic - 200mm	Door - Frame/Mullion	Level 1		10' - 0"	899	0	₹ 18.00	₹ 12.00	₹ 30.00	₹ 26,970.00
Basic Wall: Generic - 200mm	Site - Earth	Level 1		10' - 0"	429	0	₹ 15.00	₹ 10.00	₹ 25.00	₹ 10,725.00
Basic Wall: Generic - 200mm	Wood - Teak	Level 1			2319	1521.47	₹ 120.00	₹ 40.00	₹ 160.00	₹ 371,040.00
Level 1: 20					3731	1560.58				
Basic Wall: Generic - 140mm Mason	Carpet (2)	Level 2		0' - 6"	39	0	₹ 80.00	₹ 15.00	₹ 95.00	₹ 3,705.00
Basic Wall: Generic - 140mm Mason	Door - Frame/Mullion	Level 2			140	0	₹ 18.00	₹ 12.00	₹ 30.00	₹ 4,200.00
Basic Wall: Generic - 140mm Mason	Masonry - Concrete Block	Level 2			182	83.73	₹ 65.00	₹ 25.00	₹ 90.00	₹ 7,535.70
Basic Wall: Generic - 200mm	Carpet (2)	Level 2	14' - 8"	20' - 0"	158	0	₹ 80.00	₹ 15.00	₹ 95.00	₹ 15,010.00
Basic Wall: Generic - 200mm	Ceiling Tile 600 x 600	Level 2	12' - 6"	10' - 0"	119	0	₹ 35.00	₹ 15.00	₹ 50.00	₹ 5,950.00
Basic Wall: Generic - 200mm	Door - Frame/Mullion	Level 2		10' - 0"	899	0	₹ 18.00	₹ 12.00	₹ 30.00	₹ 26,970.00
Basic Wall: Generic - 200mm	Site - Earth	Level 2	14' - 6"	10' - 0"	129	0	₹ 15.00	₹ 10.00	₹ 25.00	₹ 3,225.00
Basic Wall: Generic - 200mm	Wood - Teak	Level 2			1498	982.83	₹ 120.00	₹ 40.00	₹ 160.00	₹ 239,680.00
Level 2: 28					3163	1066.56				
Basic Wall: Generic - 200mm	Door - Frame/Mullion	Level 3		10' - 0"	197	0	₹ 18.00	₹ 12.00	₹ 30.00	₹ 5,910.00
Basic Wall: Generic - 200mm	Wood - Teak	Level 3		10' - 0"	400	262.54	₹ 120.00	₹ 40.00	₹ 160.00	₹ 64,000.00
Level 3: 6					597	262.54				
Grand total: 54					7492	2889.68			Total: Unit	₹ 788,440.60

Window Material Takeoff									
Family and Type	Material: Name	Level	Count	Width	Height	Material:Cost	Labour:Cost	Total:Rate	Total:Amount
ement 3x3 with Trim: 36" x	Glass	Level 1	4	3' - 0"	6' - 0"	₹ 1,200.00	₹ 300.00	₹ 1,500.00	₹ 6,000.00
ement 3x3 with Trim: 36" x	Sash	Level 1	4	3' - 0"	6' - 0"	₹ 2,500.00	₹ 500.00	₹ 3,000.00	₹ 12,000.00
ement 3x3 with Trim: 36" x	Trim	Level 1	4	3' - 0"	6' - 0"	₹ 800.00	₹ 200.00	₹ 1,000.00	₹ 4,000.00
ement Dbl with Trim: 32" x	Glass	Level 1	1	2' - 8"	4' - 0"	₹ 800.00	₹ 200.00	₹ 1,000.00	₹ 1,000.00
ement Dbl with Trim: 32" x	Sash	Level 1	1	2' - 8"	4' - 0"	₹ 1,800.00	₹ 400.00	₹ 2,200.00	₹ 2,200.00
ement Dbl with Trim: 32" x	Trim	Level 1	1	2' - 8"	4' - 0"	₹ 600.00	₹ 150.00	₹ 750.00	₹ 750.00
ement 3x3 with Trim: 36" x	Glass	Level 2	4	3' - 0"	6' - 0"	₹ 1,200.00	₹ 300.00	₹ 1,500.00	₹ 6,000.00
ement 3x3 with Trim: 36" x	Sash	Level 2	4	3' - 0"	6' - 0"	₹ 2,500.00	₹ 500.00	₹ 3,000.00	₹ 12,000.00
ement 3x3 with Trim: 36" x	Trim	Level 2	4	3' - 0"	6' - 0"	₹ 800.00	₹ 200.00	₹ 1,000.00	₹ 4,000.00
ement Dbl with Trim: 32" x	Glass	Level 2	1	2' - 8"	4' - 0"	₹ 800.00	₹ 200.00	₹ 1,000.00	₹ 1,000.00
ement Dbl with Trim: 32" x	Sash	Level 2	1	2' - 8"	4' - 0"	₹ 1,800.00	₹ 400.00	₹ 2,200.00	₹ 2,200.00
ement Dbl with Trim: 32" x	Trim	Level 2	1	2' - 8"	4' - 0"	₹ 600.00	₹ 150.00	₹ 750.00	₹ 750.00
ement Dbl with Trim: 32" x	Glass	Level 3	1	2' - 8"	4' - 0"	₹ 800.00	₹ 200.00	₹ 1,000.00	₹ 1,000.00
ement Dbl with Trim: 32" x	Sash	Level 3	1	2' - 8"	4' - 0"	₹ 1,800.00	₹ 400.00	₹ 2,200.00	₹ 2,200.00
ement Dbl with Trim: 32" x	Trim	Level 3	1	2' - 8"	4' - 0"	₹ 600.00	₹ 150.00	₹ 750.00	₹ 750.00
Grand total: 33			33					Total:Unit	₹ 55,850.00