

PROJECT ESTIMATE & QUANTITY SUMMARY

PROJECT DETAILS

- Project Name : Single Story Residential Building (Kerala House Style)
- Location : Kerala, India
- Estimation Type : BIM 3D Quantity Extraction & Detailed Master BOQ

PROJECT HIGHLIGHTS

- Primary Tools Used : Autodesk Revit 3D, AutoCAD & MS Excel
- Scope of Work : Concrete, Brickwork, Doors & Windows, Flooring, Plastering
- Takeoff Workflow : Revit 3D Model Extraction -> Excel Data Processing -> Master BOQ

PORTFOLIO ATTACHMENTS INCLUDED

- * Section 01 : Architectural Drawings (Ground Floor Plan, Elevation & Section PDF)
- * Section 02 : Detailed BOQ Schedule & Costing Breakdown PDF



Scale	As indicated
-------	--------------

Grand Summary Sheet		
S.No	Description	Total Cost
1	BrickWork & Masonry	₹ 424,522.00
2	Concrete & Foundation	₹ 479,494.00
3	Door Schedule	₹ 57,500.00
4	Windows Schedule	₹ 72,000.00
5	Flooring Work	₹ 414,004.00
6	Wall Finishes & Plastering	₹ 576,360.00
	Sub-Total	₹ 2,023,880.00
	Contingencies & Miscellaneous(3%)	₹ 60,716.40
	Grand Total Estimate Cost	₹ 2,084,596.40

Door Schedule							
Family and Type	Height	Width	Count	Door unit cost	Fitting cost	Total Rate	Total amount
Double-Panel 2: md	7' - 0"	2' - 5"	1	₹ 8,000.00	₹ 500.00	₹ 8,500.00	₹ 8,500.00
M_Single-Flush: 0762 x 2032mm	6' - 8"	2' - 6"	1	₹ 5,000.00	₹ 500.00	₹ 5,500.00	₹ 5,500.00
M_Single-Flush: 0762 x 2032mm	6' - 8"	2' - 6"	1	₹ 5,000.00	₹ 500.00	₹ 5,500.00	₹ 5,500.00
M_Single-Flush: 0762 x 2032mm	6' - 8"	2' - 6"	1	₹ 5,000.00	₹ 500.00	₹ 5,500.00	₹ 5,500.00
M_Single-Flush: bathroom	6' - 8"	2' - 0"	1	₹ 3,000.00	₹ 500.00	₹ 3,500.00	₹ 3,500.00
M_Single-Flush: 0762 x 2032mm	6' - 8"	2' - 6"	1	₹ 5,000.00	₹ 500.00	₹ 5,500.00	₹ 5,500.00
M_Single-Flush: 0762 x 2032mm	6' - 8"	2' - 6"	1	₹ 5,000.00	₹ 500.00	₹ 5,500.00	₹ 5,500.00
M_Single-Flush: bathroom	6' - 8"	2' - 0"	1	₹ 3,000.00	₹ 500.00	₹ 3,500.00	₹ 3,500.00
M_Single-Flush: 0762 x 2032mm	6' - 8"	2' - 6"	1	₹ 5,000.00	₹ 500.00	₹ 5,500.00	₹ 5,500.00
M_Single-Flush: bathroom	6' - 8"	2' - 0"	1	₹ 3,000.00	₹ 500.00	₹ 3,500.00	₹ 3,500.00
M_Single-Flush: 0762 x 2032mm	6' - 8"	2' - 6"	1	₹ 5,000.00	₹ 500.00	₹ 5,500.00	₹ 5,500.00
						Total Amount	₹ 57,500.00

Window Schedule							
Family and Type	Height	Width	Area	Count	Material Rate	Labour Rate	Total Cost
Casement 3x3 with Trim: mdclass	5	2	10	1	₹ 250.00	₹ 50.00	₹ 3,000.00
Casement 3x3 with Trim: mdclass	5	2	10	1	₹ 250.00	₹ 50.00	₹ 3,000.00
Casement 3x3 with Trim: mdside	2	1	2	1	₹ 250.00	₹ 50.00	₹ 600.00
Casement 3x3 with Trim: mdside	2	1	2	1	₹ 250.00	₹ 50.00	₹ 600.00
Casement 3x3 with Trim: mdside	2	1	2	1	₹ 250.00	₹ 50.00	₹ 600.00
Casement 3x3 with Trim: mdclass	5	2	10	1	₹ 250.00	₹ 50.00	₹ 3,000.00
Casement 3x3 with Trim: mdclass	5	2	10	1	₹ 250.00	₹ 50.00	₹ 3,000.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
Casement 3x3 with Trim: 36" x 48"	4	3	12	1	₹ 250.00	₹ 50.00	₹ 3,600.00
						Grand Total	₹ 72,000.00

Wall Schedule								
Family and Type	Length	Area	Volume	Material Rate/(SF)	Material Amount	Labour Rate/(SF)	Labour Amount	Total Amount
Basic Wall: Foundation - 300mm Concrete	39' - 0"	78	76.77	₹ 50	₹ 3,900.00	₹ 40.00	₹ 3,120.00	₹ 7,020.00
Basic Wall: 9"	31' - 0 1/2"	301	197.41	₹ 135	₹ 40,635.00	₹ 35.00	₹ 10,535.00	₹ 51,170.00
Basic Wall: 9"	15' - 8"	155	101.89	₹ 135	₹ 20,925.00	₹ 35.00	₹ 5,425.00	₹ 26,350.00
Basic Wall: 9"	14' - 0"	139	90.92	₹ 135	₹ 18,765.00	₹ 35.00	₹ 4,865.00	₹ 23,630.00
Basic Wall: 9"	11' - 8"	112	73.2	₹ 135	₹ 15,120.00	₹ 35.00	₹ 3,920.00	₹ 19,040.00
Basic Wall: 9"	34' - 4 1/2"	333	218.04	₹ 135	₹ 44,955.00	₹ 35.00	₹ 11,655.00	₹ 56,610.00
Basic Wall: 9"	8' - 9"	100	65.49	₹ 135	₹ 13,500.00	₹ 35.00	₹ 3,500.00	₹ 17,000.00
Basic Wall: 9"	8' - 4 1/2"	85	55.6	₹ 135	₹ 11,475.00	₹ 35.00	₹ 2,975.00	₹ 14,450.00
Basic Wall: Foundation - 300mm Concrete	35' - 3"	72	70.37	₹ 50	₹ 3,600.00	₹ 40.00	₹ 2,880.00	₹ 6,480.00
Basic Wall: 9"	14' - 0"	130	85.49	₹ 135	₹ 17,550.00	₹ 35.00	₹ 4,550.00	₹ 22,100.00
Basic Wall: 9"	14' - 0"	139	91.51	₹ 135	₹ 18,765.00	₹ 35.00	₹ 4,865.00	₹ 23,630.00
Basic Wall: 9"	3' - 4"	40	26.39	₹ 135	₹ 5,400.00	₹ 35.00	₹ 1,400.00	₹ 6,800.00
Basic Wall: 9"	5' - 8"	62	40.83	₹ 135	₹ 8,370.00	₹ 35.00	₹ 2,170.00	₹ 10,540.00
Basic Wall: 9"	4' - 8"	31	20.12	₹ 135	₹ 4,185.00	₹ 35.00	₹ 1,085.00	₹ 5,270.00
Basic Wall: 9"	2' - 10"	28	18.04	₹ 135	₹ 3,780.00	₹ 35.00	₹ 980.00	₹ 4,760.00
Basic Wall: 9"	0' - 11"	10	6.58	₹ 135	₹ 1,350.00	₹ 35.00	₹ 350.00	₹ 1,700.00
Basic Wall: 9"	10' - 8"	90	58.8	₹ 135	₹ 12,150.00	₹ 35.00	₹ 3,150.00	₹ 15,300.00
Basic Wall: Foundation - 300mm Concrete	38' - 5 1/2"	76	74.74	₹ 50	₹ 3,800.00	₹ 40.00	₹ 3,040.00	₹ 6,840.00
Basic Wall: Foundation - 300mm Concrete	14' - 2"	26	25.98	₹ 50	₹ 1,300.00	₹ 40.00	₹ 1,040.00	₹ 2,340.00
Basic Wall: Generic - 200mm	10' - 8"	34	22.27	₹ 90	₹ 3,060.00	₹ 25.00	₹ 850.00	₹ 3,910.00
Basic Wall: Generic - 200mm	10' - 8"	32	20.98	₹ 90	₹ 2,880.00	₹ 25.00	₹ 800.00	₹ 3,680.00
Basic Wall: Generic - 200mm	30' - 7 1/2"	90	59.02	₹ 90	₹ 8,100.00	₹ 25.00	₹ 2,250.00	₹ 10,350.00
Basic Wall: 9"	14' - 0"	130	85.42	₹ 135	₹ 17,550.00	₹ 35.00	₹ 4,550.00	₹ 22,100.00
Basic Wall: 9"	11' - 8"	112	73.2	₹ 135	₹ 15,120.00	₹ 35.00	₹ 3,920.00	₹ 19,040.00
Basic Wall: 9"	22' - 3 1/2"	217	142.16	₹ 135	₹ 29,295.00	₹ 35.00	₹ 7,595.00	₹ 36,890.00
Basic Wall: 9"	27' - 11 1/2"	272	178.33	₹ 135	₹ 36,720.00	₹ 35.00	₹ 9,520.00	₹ 46,240.00
Basic Wall: 9"	7' - 8"	77	50.52	₹ 135	₹ 10,395.00	₹ 35.00	₹ 2,695.00	₹ 13,090.00
Basic Wall: 9"	14' - 0"	130	85.49	₹ 135	₹ 17,550.00	₹ 35.00	₹ 4,550.00	₹ 22,100.00
Basic Wall: 9"	5' - 8"	49	32.08	₹ 135	₹ 6,615.00	₹ 35.00	₹ 1,715.00	₹ 8,330.00
Basic Wall: 9"	4' - 8"	44	28.87	₹ 135	₹ 5,940.00	₹ 35.00	₹ 1,540.00	₹ 7,480.00
Basic Wall: 9"	5' - 8"	55	36.09	₹ 135	₹ 7,425.00	₹ 35.00	₹ 1,925.00	₹ 9,350.00
Basic Wall: Generic - 200mm	3' - 9"	11	7.37	₹ 90	₹ 990.00	₹ 25.00	₹ 275.00	₹ 1,265.00
Basic Wall: Generic - 200mm	14' - 0"	42	27.59	₹ 90	₹ 3,780.00	₹ 25.00	₹ 1,050.00	₹ 4,830.00
Basic Wall: Generic - 200mm	12' - 1"	34	22.47	₹ 90	₹ 3,060.00	₹ 25.00	₹ 850.00	₹ 3,910.00
Basic Wall: 9"	8' - 0"	75	49.24	₹ 135	₹ 10,125.00	₹ 35.00	₹ 2,625.00	₹ 12,750.00
Basic Wall: Generic - 200mm	10' - 8"	73	47.95	₹ 90	₹ 6,570.00	₹ 25.00	₹ 1,825.00	₹ 8,395.00
Basic Wall: Generic - 200mm	10' - 8"	23	14.76	₹ 90	₹ 2,070.00	₹ 25.00	₹ 575.00	₹ 2,645.00
Basic Wall: 9"	4' - 9"	49	31.88	₹ 135	₹ 6,615.00	₹ 35.00	₹ 1,715.00	₹ 8,330.00
Basic Wall: Generic - 200mm	5' - 8"	55	36.09	₹ 90	₹ 4,950.00	₹ 25.00	₹ 1,375.00	₹ 6,325.00
Basic Wall: Foundation - 300mm Concrete	24' - 6"	48	47.24	₹ 50	₹ 2,400.00	₹ 40.00	₹ 1,920.00	₹ 4,320.00
							Grand Total	₹ 576,360.00

Floor Schedule							
Family and Type	Area	Volume	Material Rate	Material Amount	Labour RATE	Labour Amount	Total Amount
Floor: Generic 150mm	742	364.94	₹ 130.00	₹ 47,442.20	₹ 40.00	₹ 14,597.60	₹ 62,039.80
Floor: Generic 150mm	3240	1594.49	₹ 130.00	₹ 207,283.70	₹ 40.00	₹ 63,779.60	₹ 271,063.30
r: Concrete-Commercial 362	52	61.44	₹ 130.00	₹ 7,987.20	₹ 40.00	₹ 2,457.60	₹ 10,444.80
Floor: Generic 150mm	842	414.45	₹ 130.00	₹ 53,878.50	₹ 40.00	₹ 16,578.00	₹ 70,456.50
						Grand Total	₹ 414,004.40

Floor Material Takeoff						
Material: Name	Material: Area	Material: Volume	Material Rate	Labour Rate	Matrial Cost	Labour Cost
Default Floor	742	364.94	₹ 65.00	₹ 20.00	₹ 48,230.00	₹ 14,840.00
wall_ligt_sandal	742	0	₹ 55.00	₹ 18.00	₹ 40,810.00	₹ 13,356.00
Default Floor	3240	1594.49	₹ 65.00	₹ 20.00	₹ 210,600.00	₹ 64,800.00
Vapour / Moisture Barriers - Damp-proofing	52	0	₹ 12.00	₹ 5.00	₹ 624.00	₹ 260.00
Site - Sand	52	2.04	₹ 45.00	₹ 10.00	₹ 2,340.00	₹ 520.00
Concrete - Cast In Situ	52	33.95	₹ 140.00	₹ 35.00	₹ 7,280.00	₹ 1,820.00
Site - Hardcore	52	25.46	₹ 35.00	₹ 12.00	₹ 1,820.00	₹ 624.00
Default Floor	842	414.45	₹ 65.00	₹ 20.00	₹ 54,730.00	₹ 16,840.00
				Matriel Total Cost	₹ 366,434.00	
				Labour Total cost	₹ 113,060.00	
				Grand Total	₹ 479,494.00	